



NOTES:

1. CONSTRUCT TRANSVERSE SAWED JOINTS @ 20' (MAX.).
2. EXPANSION JOINTS TO BE PLACED AT ALL INTERSECTIONS.
3. MACHINE FINISHED CONCRETE SHALL HAVE A MAXIMUM SLUMP OF 4 INCHES AND A MIN. 3600 PSI COMPRESSIVE STRENGTH AT 28 DAYS, WITH UP TO 20% TYPE C FLY ASH REPLACEMENT ALLOWED.
4. HAND FINISHED CONCRETE SHALL HAVE A MAXIMUM SLUMP OF 5 INCHES AND A MIN. 3600 PSI COMPRESSIVE STRENGTH AT 28 DAYS. NO FLY ASH ALLOWED IN HAND FINISHED CONCRETE.



**PAVING CONSTRUCTION DETAILS**  
**TYPICAL ALLEY**

REVISION DATE:  
2/1/2024

SHEET: P-09